Room schedule		
No.	Room	Area, m²
1	Entrance hall	9,07
2	Kitchen, dining and living room	45,37
3	Corridor	10,12
4	Technical room	6,48
5	Bathroom with WC	9,36
6	Study	11,81
7	Children's room 1	12,06
8	Children's room 2	12,06
9	Main bedroom	14,87
Total		131,21

Window schedule				
Mark	Type	Width, mm	Height, mm	Count, pcs
L-1	PVC window 3050 x 1500, triple glazed	3050	1500	1
L-2	PVC window 1800 x 1200, triple glazed	1800	1200	1
L-3	PVC window 1500 x 1500, triple glazed	1500	1500	4
L-4	PVC window 1800 x 1500, triple glazed	1800	1500	1
L-5	PVC window 1200 x 1500, triple glazed	1200	1500	1
L-6	PVC window 500 x 2100, triple glazed	500	2100	1
L-7	PVC window 900 x 600, triple glazed	900	600	1
L-8	PVC window 600 x 600, triple glazed	600	600	1

Total: 11

Door schedule				
Mark	Type	Width, mm	Height, mm	Count, pcs
D-1	Entrance door, steel, insulated, no glass, thermally broken, U ≤ 1.0, 1000×2100	1000	2100	1
D-2	Interior door 800 x 2100	800	2100	6
D-3	Terrace entrance door, steel, insulated, no glass, thermally broken, U ≤ 1.0, 1000×2100	1000	2100	1

Total: 8

Material quantities — walls		
Material	Area, m²	Volume, m³
Aerated concrete Bauroc D400	254,57	52,73
Breathable (wind barrier) membrane	85,45	0,00
Facade stone wool	160,14	23,32
Gypsum plaster	361,39	4,24
OSB board	12,47	0,19
Siberian larch, vertical facade boards 22x140	89,70	1,91
Softwood battens	89,68	2,44
Thin-layer facade render	74,72	0,35
Vent grille, aluminium, white	0,40	0,01
Vent strip / mesh	0,30	0,00

Material quantities — base and floors		
Material	Area, m²	Volume, m³
Ceramic tiles, light grey	24,91	0,25
Crushed stone	160,00	48,00
Extruded polystyrene (XPS)	215,00	50,53
Impregnated softwood C24 (joists)	25,27	3,66
Laminate, oak	106,30	1,06
Reinforced concrete C25/30	160,00	15,01
Siberian larch, decking 28x145	25,27	0,71
Vent strip / mesh	1,80	0,01

Material quantities — roof		
Material	Area, m²	Volume, m³
Breathable (wind barrier) membrane	222,30	0,00
Coated steel, standing seam roofing	222,30	0,22
Softwood battens	222,30	16,67

Material quantities — attic floor		
Material	Area, m²	Volume, m³
Blown stone wool	144,64	58,06
Membrane / vapour barrier	135,60	0,00
Plasterboard 12.5 mm	135,60	1,70
Softwood battens	135,60	6,78

Designer (company, reg. No. / name, certificate No.)
Construction specialist— to be confirmed (name, practice certificate No.)

Project, address
Detached house "Priede 130"— single-family dwelling, group II
Latvia, address and cadastral designation— to be confirmed

Drawing title
Room schedule. Window, door and material schedules

Drawn by	Stage	Scale	Date	Code, sheet
planpris	Sketch	—	13.09.2026	EN-AR-5
Discipline lead				sheet 5 of 8
—				